

河南省理工学校卫生间隔断清单

序号	楼号	楼层	男卫 (个)	女卫 (个)	数量	单位	备注
1	北教学楼	1F东	5	5	12.95	m ²	
		2F东	5	5	12.95	m ²	
		2F西	5	5	12.95	m ²	
		3F东	5	5	12.95	m ²	
		3F西	5	5	12.95	m ²	
		4F东	5	5	12.95	m ²	
		4F西	5	5	12.95	m ²	
		5F东	5	5	12.95	m ²	
		5F西	5	5	12.95	m ²	
		6F东	5	5	12.95	m ²	
		6F西	5	5	12.95	m ²	
	拆除旧隔断		55	55	110	个	
	垃圾清运				1	车	
	合计		55	55	142.45	m ²	
2	南教学楼	1F	4	5	12.95	m ²	
		2F	4	5	12.95	m ²	
		3F	4	5	12.95	m ²	
		4F	4	5	12.95	m ²	
		5F	4	5	12.95	m ²	
		6F	4	5	12.95	m ²	
	拆除旧隔断		24	30	54	个	
	垃圾清运				1	车	
	合计		24	30	77.7	m ²	
		1F	10		14.25	m ²	1、板材：16mm实芯 共挤板 2、隔断底部用70mm 铝合金脚套固定 3、板材同色PVC收边 4、角码螺丝用穿丝 5、板材与板材交接处
		2F	10		14.25	m ²	
		3F	10		14.25	m ²	

3	4号男公寓楼	4F	10		14.25	m ²	打结构胶 6、墙面处理
		5F	10		14.25	m ²	
		6F	10		14.25	m ²	
		7F	10		14.25	m ²	
	拆除旧隔断		70		70	个	
	垃圾清运				1	车	
	合计		70		99.75	m ²	
4	5号女公寓楼	1F		7	9.75	m ²	
		2F		7	9.75	m ²	
		3F		7	9.75	m ²	
		4F		7	9.75	m ²	
		5F		7	9.75	m ²	
		6F		7	9.75	m ²	
	拆除旧隔断			42	42	个	
	垃圾清运				1	车	
	合计			42	58.5	m ²	
5	小东楼	3F	5	4	11.25	m ²	
		4F	5	4	11.25	m ²	
		5F	5	4	11.25	m ²	
	拆除旧隔断		15	12	27	个	
	垃圾清运				1	车	
	合计		15	12	33.75	m ²	